BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Negotiated SCHEDULE-B

Name of Work :- Improvements of approach road at Nelamaheshwaramma temple front side & back side road in dasarahalli in ward no. 15

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				IN Figure	In words
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and eletrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	14.69	299.98	Rupees Two hundred ninety nine and Ninghty eight Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	3.67	5159.02	Rupees Five Thousand One hundred Fifty Nine and Two Paise Only
3	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.70 cum and fine aggregtes @ 0.47 cum,with superlastiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in laye` not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plaste`, columns, pie`, abutments, pilla`, posts, struts, buttresses, string or lacing cou`es, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	14.69	6594.26	Rupees Six Thousand Five hunded ninghty four and Twenty six Paise Only
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	0.88	66482.14	Rupees Sixty Six thousand Four hundred Eighty two and Fourteen Paise Only
5	M S Plate	KG	272.00	43.46	Rupees Fourty three and Fourty six Paise Only
6	G I Pipe 150mm Dia B Class	Mtr	68.00	1274.12	Rupees One Thousand two hundred Seventy four and Twelve Paise Only
7	M S Bolts & nuts	Kgs	60.00	84.00	Rupees Eighty Four rupees Only
8	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	Sqm	10.20	88.56	Rupees Eighty eight and Fifty six Paise only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	14.69	85.65	Rupees Eighty Five nd Sixty Five Paise Only

Signature of Contractor

Exicutive Engineer
Dasarahalli

Scanned by CamScanner